
MANCHESTER MANOR

DRAINAGE IMPROVEMENTS

BROAD CREEK / CHESAPEAKE BAY WATERSHED SUSSEX COUNTY, DELAWARE




PLAN INDEX MAP


SHEET INDEX

<u>TITLE</u>
COVER SHEET
PROJECT SITE PLAN OVERVIEW
SITE PLAN - W
SITE PLAN - NE
SITE PLAN - SE
MANCHESTER LANE PROFILES
KENSINGTON WAY PROFILES
KINGS MILL DR. & MISC PROFILES
PROPERTY LINE & LANDSCAPE BUFFER PROFILES
DITCHES 1, 2,, & 3 PROFILES
POND PROFILE & DETAILS
CONSTRUCTION DETAILS AND NOTES
CONSTRUCTION DETAILS AND NOTES
EROSION & SEDIMENT CONTROL PLAN OVERVIEW
EROSION & SEDIMENT CONTROL PLAN - N
EROSION & SEDIMENT CONTROL PLAN - NE
EROSION & SEDIMENT CONTROL PLAN - SE
EROSION & SEDIMENT CONTROL DETAILS & NOTES
EROSION & SEDIMENT CONTROL DETAILS & NOTES
EROSION & SEDIMENT CONTROL DETAILS & NOTES
EROSION & SEDIMENT CONTROL DETAILS & NOTES

EXISTING BUILDING BOTTOM WIDTH LEFT BOTTOM WIDTH RIGHT CENTERLINE DITCH CENTERLINE DITCH STATION MAJOR CENTERLINE DITCH STATION MINOR CENTERLINE ROAD CONTOUR MAJOR CONTOUR MINOR CONCRETE EDGE OF GRAVEL **FENCELINE** GEOMORPHOLOGY FEATURE HYDROLOGIC DRAINAGE AREA HYDROLOGIC SOIL TYPE HYDROLOGIC SOIL GROUP HYDROLOGIC TIME OF CONCENTRATION **MARSHLINE** PROPERTY LINE RAILROAD TRACKS SHEETPILE SIDEWALK SIGN STORMWATER PIPE STORMWATER STRUCTURE TAX DITCH RIGHT-OF-WAY TAX DITCH SPECIAL RIGHT-OF-WAY -------TOP OF BANK RIGHT TOP OF BANK LEFT TEXT UTILITY: COMMUNICATION CABLE C — COMM — UTILITY: OVERHEAD WIRE UTILITY POLE UTILITY: ELECTRIC EO>O - E - E -UTILITY: GAS — S — S — UTILITY: SANITARY SEWER S ss ___ W____ W___ UTILITY: WATER MATCHLINE WATERSHED DRAINAGE AREA SOIL BORING WETLAND CROSS-SECTION

WOODSLINE





LOCATION MAP

PERMITTEE CERTIFICATION:

I, THE UNDERSIGNED, CERTIFY THAT ALL LAND CLEARING AND CONSTRUCTION SHALL BE DONE PURSUANT TO THE APPROVED PLAN AND THAT RESPONSIBLE PERSONNEL (I.E., BLUE CARD HOLDER) INVOLVED IN THE LAND DISTURBANCE WILL HAVE A CERTIFICATION OF TRAINING PRIOR TO INITIATION OF THE PROJECT, AT A DNREC SPONSORED OR APPROVED TRAINING COURSE FOR THE CONTROL OF EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION. IN ADDITION, I GRANT THE DEPARTMENT OR DELEGATED INSPECTION AGENCY THE RIGHT TO CONDUCT ON—SITE INSPECTIONS, AND I UNDERSTAND MY RESPONSIBILITIES UNDER THE NPDES CONSTRUCTION GENERAL PERMIT.

NAME	TITLE
SIGNATURE	DATE

LICENSED PROFESSIONAL CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN HAS BEEN PREPARD UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLIES WITH THE APPLICABLE STATE AND LOCAL REGULATIONS AND ORDINANCES.

AMELIA REED, PE NAME	<u>DNREC — DIVISION ENGINEER IV</u> TITLE
SIGNATURE	DATE

REVISIONS

DESCRIPTION

2.22 re-design gravity option

2.2 DNREC COMMENTS

3.22 DNREC COMMENTS

9.22 DNREC COMMENTS

DNREC COMMENTS



JWN, DE 19957 2-856-0951 1ed Stewardship .m

DNREC - Division of Watershe
Dover Office





NAGE IMPROVEMENTS, # 21-22 Creek / Nanticoke watersj SSEX County, Delaware

Date: 2/04/2022

Designed: JE

lanned: JE / KW / JG / TB





DATE DESCRIPTION

5.12.22 re-design gravity option

10.22 DNREC COMMENTS

11.8.22 DNREC COMMENTS

12.9.22 DNREC COMMENTS / OMISSIONS

Conservation district

4, DE 19957 5-0951 | Stewardship

SUSSEX CONSERVATION DISTRICT
23818 SHORTLY RD., GEORGETOWN, DE 19957
PHONE: (302)-856-2105 FAX: (302-856-0951

NREC - Division of Watershed Stewardsh

Drainage Program



HESTER MANOR
I IMPROVEMENTS, # 21-229
K / NANTICOKE WATERSHEI
COUNTY, DELAWARE

DRAINAGE IMPROBROAD CREEK / NAI

ate: 2/04/2022 esigned: JE

Designed: JE

Planned: JE / KW / JG / TB

Drawn: JE

EPTIC DRAIN FIELD ARE




DNREC



ate: 2/04/2022 esigned: JE ned: JE/KW/JG/TB

PLAN VIEW



DATE DESCRIPTION

5.12.22 re—design gravity option
10.22 DNREC COMMENTS
11.8.22 DNREC COMMENTS
12.9.22 DNREC COMMENTS / OMISSIONS

rdship conserve

RVATION DISTRICT
"GEORGETOWN, DE 19957
5-2105 FAX: (302-856-0951

DNREC - Division of Watershed Stewardsh

Drainage Program

Dover Office

Beiser Blvd Swite 102 Phone: 3023/239-9021 21309 Berlin Bd Hnit 6 Phone: 3020

STANTINGENT OF NATIONAL STANTI

ESTEK MANOK Aprovements, # 21-229 Nanticoke watershed Junty, delaware

DRAINAGE IMPROVEME ROAD CREEK / NANTICOK SUSSEX COUNTY, DE

Date: 2/04/2022

Designed: JE


Planned: JE / KW / JG / TB


Drawn: JE


PLAN VIEW


SCALE: 1" = 50'

50 100 150









LANDSCAPE BUFFER PROFILE

DNREC

2/04/2022 anned: JE / KW / JG / TB

SCALE: 1" = 50'

LEDGEND DESIGN SLOPE EXISTING ROAD SWALE GRADE — — — EXISTING ROAD CL EXISTING GRADE EXISTING LEFT TOB


EXISTING RIGHT TOB _ _ _


0.16% —— 15" HDPE-135.6LF P37 4+00 0+00 DITCH 1 PROFILE SCALE 1" = 50'

STATION 2+50.00 ELEVATION 23.49

DITCH 2 PROFILE

SCALE 1" = 50'







FES 2-14 TO DI 2-15 PROFILE

SCALE 1" = 50'

LEDGEND DESIGN SLOPE EXISTING ROAD SWALE GRADE - - - - -EXISTING ROAD CL EXISTING GRADE ____ EXISTING LEFT TOB ----EXISTING RIGHT TOB ----


File Location: G:\Equipment Section\Projects\MANCHESTER MANOR - NAVARRO, 21-229\dwg\MANCHESTER MANOR 2.dwg Layout:PROFILE 5 User: james.elliott Plot time: 12-09-22 @ 2:31pm


SUSSEX CONSERVATION DISTRICT
23818 SHORTLY RD., GEORGETOWN, DE 19957





2/04/2022

nned: JE/KW/JG/TB









DATE DESCRIPTION

5.12.22 re-design gravity option
10.22 DNREC COMMENTS
11.8.22 DNREC COMMENTS
12.9.22 DNREC COMMENTS / OMISSIONS



23818 SHORTLY RD., GEORGETOWN, DE 19957
PHONE: (302)-856-2105 FAX: (302-856-0951
C - Division of Watershed Stewardship
Drainage Program

over Office
Georgetown Office
Suite 102 Phone: (302) 739-9921 21309 Berlin Rd. Unit 6 Phone: (302) 855




MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
SOAD CREEK / NANTICOKE WATERSHED
SUSSEX COUNTY, DELAWARE

Date: 2/04/2022


Designed: JE

awn: JE
neet No. **C-205**


nned: JE / KW / JG / TB



DITCH TYPICAL CROSSING SECTION



SWALE TYPICAL CROSSING SECTION



	STRUCTURE SCHEDULE									
NAME	NORTHING	EASTING	RIM ELEV(FT)	BASE ELEV(FT	Γ) INV-IN ELEV(FT) (1) INV-IN ELEV(FT) (2	NINV-OUT ELEV(FT)	TYPE		
DI 2-20	205687.09	618736.48	25.28	21.70	N/A	N/A	22.20	24" NYLOPLAST DRAIN BASIN		
DI 2-17	205872.17	619188.02	N/A	N/A	N/A	N/A	23.10	FES WITH BAR GUARD		
DI 2-15	205831.63	619317.44	26.50	21.90	22.75	22.65	22.40	PWBD-2		
DI 2-14	205847.24	619563.80	N/A	N/A	N/A	N/A	22.75	FES WITH BAR GUARD		
DI 2-13	205874.58	619477.13	25.77	21.55	22.55	N/A	22.55	24" NYLOPLAST DRAIN BASIN		
DI 2-12	205906.31	619376.14	27.06	21.25	22.25	N/A	22.25	24" NYLOPLST DRAIN BASIN		
DI 2-11	205821.65	619349.25	27.10	21.28	22.30	22.00	21.78	PWBD-2		
DI 2-10	205669.29	619297.48	25.77	19.46	21.46	N/A	21.46	24" NYLOPLAST DRAIN BASIN		
DI 2-9	205607.95	619224.01	26.29	20.27	21.27	N/A	21.27	24" NYLOPLAST DRAIN BASIN		
DI 2-8	205593.59	619149.10	26.63	20.12	21.12	N/A	21.12	24" NYLOPLAST DRAIN BASIN		
DI 2-7	205622.49	618928.79	25.54	19.70	20.70	N/A	20.70	24" NYLOPLAST DRAIN BASIN		
DI 2-6	205650.61	618730.79	24.76	19.20	20.20	22.00	20.20	30" NYLOPLAST DRAIN BASIN		
DI 2-5	205697.31	618393.16	24.00	18.60	19.60	N/A	19.10	PWBD-2		
DI 2-4	205736.68	618062.09	23.00	17.75	18.85	N/A	18.35	PWBD-4		
DI 2-3	205715.46	618047.61	23.00	17.80	18.30	N/A	18.30	PWBD-4		
DI 2-2	205722.32	618003.54	23.00	17.75	18.25	N/A	18.25	PWBD-2		
DI 2-1	205737.33	617957.08	N/A	N/A	N/A	N/A	18.12	Outfall		

	PIPE SCHEDULE									
VAME	UP STRUCTURE	UP INVERT (FT)	DN STRUCTURE	DOWN INVERT (FT)	SIZE (IN)	LENGTH (FT)	SLOPE (%)	MATERIAL		
P22	DI 2-2	18.25	DI 2-1	18.12	36.0	48.82	0.270	HDPE		
P23	DI 2-3	18.30	DI 2-2	18.25	36.0	44.60	0.112	HDPE		
P24	DI 2-4	18.35	DI 2-3	18.30	36.0	25.69	0.184	HDPE		
P25	DI 2-5	19.10	DI 2-4	18.85	30.0	333.40	0.076	HDPE		
P26	DI 2-6	20.20	DI 2-5	19.60	24.0	340.85	0.176	HDPE		
P27	DI 2-7	20.70	DI 2-6	20.20	24.0	199.99	0.250	HDPE		
P28	DI 2-8	21.12	DI 2-7	20.70	24.0	222.20	0.189	HDPE		
P29	DI 2-9	21.27	DI 2-8	21.12	24.0	76.27	0.197	HDPE		
P30	DI 2-10	21.46	DI 2-9	21.27	24.0	95.72	0.199	HDPE		
P31	DI 2-11	21.78	DI 2-10	21.46	24.0	160.91	0.199	HDPE		
P32	DI 2-12	22.25	DI 2-11	22.00	15.0	88.83	0.281	HDPE		
P33	DI 2-13	22.55	DI 2-12	22.25	15.0	105.86	0.283	HDPE		
P34	DI 2-14	22.75	DI 2-13	22.55	15.0	90.88	0.220	HDPE		
P35	DI 2-15	22.40	DI 2-11	22.30	18.0	33.33	0.300	HDPE		
P36	DI 2-16	22.75	DI 2-15	22.65	15.0	24.18	0.414	HDPE		
P37	DI 2-17	23.10	DI 2-15	22.75	15.0	135.63	0.258	HDPE		
P40	DI 2-20	22.20	DI 2-6	22.00	15.0	36.93	0.542	HDPE		
P41	_	26.62	_	26.52	8.0	30.0	0.33	HDPE		
P42	_	26.28	_	26.18	8.0	30.0	0.33	HDPE		
P43	_	25.68	_	25.52	8.0	30.0	0.167	HDPE		
P44	_	25.82	_	25.77	8.0	30.0	0.167	HDPE		
P45	_	23.25	_	23.18	12.0	30.0	0.233	HDPE		
P46	_	23.63	_	23.41	12.0	30.0	0.233	HDPE		
P47	_	24.18	_	24.11	12.0	30.0	0.233	HDPE		
P48	_	24.67	_	24.60	12.0	30.0	0.233	HDPE		
P49	_	23.61	_	23.54	12.0	30.0	0.233	HDPE		
P50	_	25.15	_	25.10	12.0	30.0	0.233	HDPE		
P51	_	25.33	_	25.28	14×9	24.0	0.167	ECMP		
P52	_	25.55	_	25.49	14x9	24.0	0.167	ECMP		
P53	_	24.42	_	24.34	14x9	24.0	0.267	ECMP		
P54	_	20.20	_	20.00	24	120.0	0.167	HDPE		
P55	_	23.60	_	23.53	12	30.0	0.1433	HDPE		

DATE

5.12.22

10.22

11.8.22

DNREC COMMENTS

12.9.22

DNREC COMMENTS

12.9.22

DNREC COMMENTS

12.9.22

DNREC COMMENTS

12.9.22

Conservation 110 D D S.1 CONSERVE.

d Stewardship


SUSSEX CONSERVATION DIS 23818 SHORTLY RD., GEORGETOWN, DE 1 PHONE: (302)-856-2105 FAX: (302-856-0951 DNREC - Division of Watershed Ste Drainage Program





MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
COAD CREEK / NANTICOKE WATERSHE
SUSSEX COUNTY, DELAWARE


: 2/04/2022 gned: JE

anned: JE/KW/JG/TB
rawn: JE










PIPE / STRUCTURE NOTES:

- 1. ALL PIPE UNLESS OTHERWISE NOTED SHALL BE ADS N-12 OR APPROVED EQUAL. ALL FITTINGS AND JOINTS SHALL BE WATERTIGHT, EXCEPT THE TWO NOTED AS SOILTIGHT. IN ADDITION, ALL JOINTS FOR PIPES DEEPER THAN 4' BELOW GRADE MUST BE MINIMUM 2' IN LENGTH AND WRAPPED IN GEOTEXTILE FABRIC MEETING DE-ESC GD-II REQUIREMENTS.
- 2. ALL CATCHBASINS UNLESS OTHERWISE NOTED SHALL BE PER DELDOT STD NO D-4 AND D-5, LATEST EDITION. THE GRATES SHALL BE TYPE 1 AND THE TOP
- 3. ALL MANHOLES UNLESS OTHERWISE NOTED SHALL BE PER DELDOT STD NO D-6, BOX MANHOLE WITH A SOLID RIM. 4. ALL FLARED ENDSECTIONS, UNLESS OTHERWISE NOTED, SHALL BE ADS OR
- APPROVED EQUAL AND MATCH THE PIPE SIZE. 5. COVERSLABS ARE NOT REQUIRED FOR ALL CATCHBASINS AND MANHOLES.
- 6. STEPS SHALL BE ADDED TO ALL CATCHBASINS AND MANHOLES ALONG A SOLID
- 7. ALL MANHOLE RIMS SHALL MATCH EXISTING GRADE. TOP ELEVATIONS LISTED MAY BE +/-.
- 8. PIPE BACKFILL SHALL BE CLASS C BEDDING PER DELDOT STD NO D-8 WITH MIN. 6" LOOSE SAND OR TYPE C BORROW.
- 9. ALL NYLOPLAST DRAIN BASINS SHALL BE INSTALLED PER NYLOPLAST H-20 LOADING INSTALLATION GUIDELINES.






MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
BROAD CREEK / NANTICOKE WATERSHEL
SUSSEX COUNTY, DELAWARE

2/04/2022 ed: JE/KW/JG/TB

C-501





SUSSEX CONSERVATION DISTRICT 23818 SHORTLY RD GEORGETOWN DE 19957

DNREC



2/04/2022 ned: JE / KW / JG / TB

C-701



2/04/2022

ined: JE / KW / JG / TB C-702

File Location: G:\Equipment Section\Projects\MANCHESTER MANOR - NAVARRO, 21-229\dwg\MANCHESTER MANOR 2.dwg Layout:ESC-NE User: james.elliott Plot time: 12-09-22 @ 2:31pm

PLAN VIEW



SUSSEX CONSERVATION DI 23818 SHORTLY RD., GEORGETOWN, DI PHONE: (302)-856-2105 FAX: (302-856-095 DNREC - Division of Watershed St

CESTANDA TO LINEAR TO THE PARTY OF THE PARTY

MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
DAD CREEK / NANTICOKE WATERSHED
SUSSEX COUNTY, DELAWARE


Date: 2/04/2022

Designed: JE

Planned: JE / KW / JG / TB

Prawn: JE

Cheet No.



Standard Detail & Specifications

Spill Control

be prominently posted.

DNREC 24-Hour Toll Free Number

Notes (cont.)

6. Education

Source:

Adapted from USEPA

Pub. 840-B-92-002

Construction Site Waste Mgt &

shall be prominently posted in the construction trailer.

DNREC Solid & Hazardous Waste Management Section

Symbol:

e. Contact information for reporting spills through the DNREC 24-Hour Toll Free Number shall

a. Best management practices for construction site pollution control shall be a part of regular

b. Information regarding waste management, equipment maintenance and spill prevention

CONTACT INFORMATION

800-662-8802

302-739-9403

DE-ESC-3.6.1

Sheet 5 of 5

Effective FEB 2019

DELAWARE EROSION Standard Detail & Specifications Construction Site Waste Mgt & Spill Control

Pollution Prevention - Spill Prevention

- Fueling should only take place in signed designated areas, away from downstream drainage facilities and watercourses.
- 2. Fueling must be with nozzles equipped with automatic shut-off to control drips. Do not top off.
- 3. Protect the areas where equipment or vehicles are being repaired, maintained, fueled or parked from storm water run-on and runoff.
- 4. Use barriers such as berms to prevent storm water run-on and runoff, and to contain spills.
- 5. Place a "Fueling Area" sign next to each fueling area.
- 6. Store hazardous materials such as fuel, solvents, oil and chemicals in secondary containment. 7. Inspect vehicles and equipment for leaks on each day of use. Repair fluid and oil leaks
- 8. Absorbent spill clean-up materials and spill kits must be available in fueling areas and on fuel
- 9. If fueling is to take place at night, make sure the fueling area is sufficiently illuminated.
- 10. Properly dispose of used oil, fluids, lubricants and spill clean-up materials. CLEAN UP SPILLS
- 1. If it is safe to do so, immediately contain and clean up any chemical and/or hazardous material
- 2. Properly dispose of used oil, fluids, lubricants and spill clean-up materials.
- 3. Do not bury spills or wash them down with water.

LEAKS AND DRIPS

- 1. Use drip pans or absorbent pads at all times. Place under and around leaky equipment.
- 2. Do not allow oil, grease, fuel or chemicals to drip onto the ground.
- 3. Have spill kits and clean up material on-site.

FILTREXX Technologies

- 4. Repair leaky equipment promptly or remove problem vehicles and equipment from the site. Clean up contaminated soil immediately.
- . Store contaminated waste in sealed containers constructed of suitable material. Label these
- 6. Clean up all spills and leaks. Promptly dispose of waste and spent clean up materials.

Source:	Symbol:	Detail No.
		DE-ESC-3.6.1
Delaware ESC Handbook		Sheet 2 of 5
		Effective FEB 2019

Standard Detail & Specifications

Construction Site Waste Mgt & Spill Control

Notes:

The Construction Site Pollution Prevention Plan should include the following elements:

1. Material Inventory

Document the storage and use of the following materials:

- a. Concrete
- b. Detergents
- c. Paints (enamel and latex)
- d. Cleaning solvents
- e. Pesticides
- f. Wood scraps
- g. Fertilizers h. Petroleum based products

2. Good housekeeping practices

- a. Store only enough product required to do the job.
- b. All materials shall be stored in a neat, orderly manner in their original labeled containers and covered.
- c. Substances shall not be mixed.
- d. When possible, all of a product shall be used up prior to disposal of the container.
- e. Manufacturers' instructions for disposal shall be strictly adhered to.
- f. The site foreman shall designate someone to inspect all BMPs daily.

3. Waste management practices


- a. All waste materials shall be collected and stored in securely lidded dumpsters in a location that does not drain to a waterbody.
- b. Waste materials shall be salvaged and/or recycled whenever possible.
- c. The dumpsters shall be emptied a minimum of twice per week, or more if necessary. The licensed trash hauler is responsible for cleaning out dumpsters.

Source:	Symbol:	Detail No.
Adapted from USEPA Pub. 840-B-92-002		DE-ESC-3.6.1 Sheet 3 of 5
		Effective FEB 2019

Standard Detail & Specifications CONTAOL Compost Log Check Dam

Construction Notes:

- Swales and channels shall be prepared in accordance with the construction specifications described in the Standards and Specifications for Temporary Berm, Temporary Swale, **Vegetated Channel**, or **Diversions**.
- than the outer edges, forming a weir that the water can flow across. The ends of the compost filter log shall wrap upslope to prevent end cutting.
- the upstream dam is at the same elevation as the top of the downstream dam. (See **Standard & Specifications for Check Dams** for design chart.)





Standard Detail & Specifications

Construction Site Waste Mgt & Spill Control

Notes (cont.)

- d. Trash shall be disposed of in accordance with all applicable Delaware laws.
- e. Trash cans shall be placed at all lunch spots and littering is strictly prohibited. Recycle bins shall be placed near the construction trailer.
- If fertilizer bags can not be stored in a weather-proof location, they shall be kept on a pallet and covered with plastic sheeting which is overlapped and anchored.

4. Equipment maintenance practices

- a. If possible, equipment should be taken to off-site commercial facilities for washing and
- b. If performed on-site, vehicles shall be washed with high-pressure water spray without detergents in an area contained by an impervious berm.
- c. Drip pans shall be used for all equipment maintenance.
- d. Equipment shall be inspected for leaks on a daily basis.
- e. Washout from concrete trucks shall be disposed of in a temporary pit for hardening and proper disposal.
- Fuel nozzles shall be equipped with automatic shut-off valves.
- g. All used products such as oil, antifreeze, solvents and tires shall be disposed of in accordance with manufacturers' recommendations and local, state and federal laws and regulations.

5. Spill prevention practices

- a. Potential spill areas shall be identified and contained in covered areas with no connection to the storm drain system.
- b. Warning signs shall be posted in hazardous material storage areas.
- c. Preventive maintenance shall be performed on all tanks, valves, pumps, pipes and other equipment as necessary.
- d. Low or non-toxic substances shall be prioritized for use.

Source:	Symbol:	Detail No.
Adapted from USEPA		DE-ESC-3.6.1
Pub. 840-B-92-002		Sheet 4 of 5
		Effective FEB 2019

EROSION AND SEDIMENT CONTROL RCD PROJECT NOTES:

- 1. THE LIMIT OF DISTURBANCE SHALL BE AS DESIGNATED ON THE PLANS. ESTIMATED LIMIT OF DISTURBANCE IS APPROXIMATELY 8.0
- ACCESS TO THE LIMIT OF DISTURBANCE AREAS SHALL BE VIA. THE SUBDIVISION STREETS. ALL STOCKPILE AREAS SHALL BE SURROUNDED ON THE DOWNSTREAM SIDE BY 12" COMPOST LOGS OR SILT FENCE AND STABILIZED WITHIN 14 DAYS OF NON-USE.
- 3. TRACKING OF SEDIMENT OFFSITE SHALL NOT BE ALLOWED. SWEEP TRACKED SEDIMENT AT THE END OF EACH DAY, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE UTILIZED MEETING THE REQUIREMENTS OF DE-ESC-3.4.7. 4. DEWATERING SHALL BE USED AS NEEDED USING A GEOTEXTILE DEWATERING BAG (DE-ESC-3.2.1.2). ALL REQUIRED DEWATERING
- PERMITS MUST BE OBTAINED PRIOR TO PUMPING.
- THE CONTRACTOR SHALL AVOID WORKING OR TRAVERSING WITHIN THE DRIPLINE OF ALL TREES. SPECIAL CARE SHALL BE USED . ALL MULCHING AND ANY ASSOCIATED NETTING MUST BE BIODEGRADABLE
- ALL DISTURBED AREAS MUST BE STABILIZED, EITHER PERMANENTLY OR TEMPORARILY, WITHIN 14 DAYS OF NON-USE OR PRIOR TO A RAIN EVENT (CROPLAND AREAS THAT WILL BE PLANTED WITH AN AGRICULTURAL CROP WITHIN 14 DAYS MAY BE STABILIZED WITH THE AGRICULTURAL CROP IN THAT TIMEFRAME). REFERENCE THE SEEDING AND MULCHING NOTES FOR ADDITIONAL INFORMATION.




NREC


MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
OAD CREEK / NANTICOKE WATERSHED
SUSSEX COUNTY, DELAWARE

2/04/2022

nned: JE / KW / JG / TB

C-704





Effective FEB 2019

Standard Detail & Specifications Vegetative Stabilization



	TEMPORARY SEEDING BY RATES, DEPTHS AND DATES												
Mix #	Species ⁶	Seedir	Seeding Rate			Optimum Seeding Dates ¹ O = Optimum Planting Period; A = Acceptable Planting Period							
	7	- 100 100		Co	astal P	lain	Р	iedmo	nt	All			
	Certified Seed	lb/Ac ⁵	lb/1000 sq.ft.	2/1- 4/30	² 5/1- 8/14	8/15- 10/31	3/1-4/30	² 5/1- 7/31	8/1- 10/31	10/31- 2/1			
1	Barley	125	4	0	А	0	0	А	0		1-2 inches 2-3" sandy soils		
2	Oats	125	4	0	Α	Α	0	Α	Α		1-2 inches 2-3" sandy soils		
3	Rye	125	4	0	А	0	0	А	0	Α	1-2 inches 2-3" sandy soils		
4	Perennial Ryegrass	125	4	0	А	0	0	А	0		0.5 inches 1-2" sandy soils		
5	Annual Ryegrass	125	4	0	Α	0	0	А	0	Α	0.5 inches 1-2" sandy soils		
6	Winter Wheat	125	4	0	А	0	0	Α	0	Α	1-2 inches 2-3" sandy soils		
7	Foxtail Millet	30 PLS	0.7		0			0		9	0.5 inches 1-2" sandy soils		
8	Pearl Millet	20 PLS	0.5		0			0			0.5 inches 1-2" sandy soils		

- 1. Winter seeding requires 3 tons per acre of straw mulch for proper stabilization.
- 2. May be planted throughout summer if soil moisture is adequate or seeded area can be irrigated.
- 3. Applicable on slopes 3:1 or less.
- 4. Fifty pounds per acre of Annual Lespedeza may be added to 1/2 the seeding rate of any of the above species.
- 5. Use varieties currently recommended for Delaware. Contact a County Extension Office for information.
- 6. Warm season grasses such as Millet or Weeping Lovegrass may be used between 5/1 and 9/1 if desired. Seed at 3-5 lbs. per acre. Good on low fertility and acid areas. Seed after frost through summer at a depth of 0.5".

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.

Source:	Symbol:	Detail No.
Delaware ESC Handbook		DE-ESC-3.4.3
		Sheet 1 of 4
		Effective FEB 2019
		*

Standard Detail & Specifications Mulching



Materials and Amounts

- a. Straw Straw shall be unrotted small grain straw applied at the rate of 1-1/2 to 2 tons per acre, or 70 to 90 pounds (two bales) per 1,000 square feet. Mulch materials shall be relatively free of weeds and shall be free of noxious weeds such as; thistles, Johnsongrass, and quackgrass. Spread mulch uniformly by hand or mechanically. For uniform distribution of hand spread mulch, divide area into approximately 1,000 square feet sections and place 70-90 pounds (two bales) of mulch in each section.
- b. Wood chips Apply at the rate of approximately 6 tons per acre or 275 pounds per 1,000 square feet when available and when feasible. These are particularly well suited for utility and road rights-of-way. If wood chips are used, increase the application rate of nitrogen fertilizer by 20 pounds of N per acre (200 pounds of 10-10-10 or 66 pounds of 30-0-0 per acre).
- c. Hydraulically applied mulch The following conditions apply to hydraulically applied mulch:
- - a. Wood fiber mulch shall consist of specially prepared wood that has been processed to a uniform state, is packaged for sale as a hydraulic mulch for use with hydraulic seeding equipment, and consists of a minimum of 70% virgin or recycled wood fiber combined with 30% paper fiber and additives.
 - Blended fiber mulch shall consist of any hydraulic mulch that contains greater than 30% paper fiber. The paper component must consist of specially prepared paper that has been processed to a uniform fibrous state and is packaged for sale as a hydraulic mulch for use with hydraulic seeding equipment.
 - c. A bonded fiber matrix (BFM) consists of long strand, specially prepared wood fibers that have been processed to a uniform state held together by a water resistant bonding agent. BFMs shall contain no paper (cellulose) mulch but may contain small percentages of synthetic fibers to enhance performance.
 - d. Refer to Figure 3.4.5a for conditions and limitations of use for each of the above categories of
- assure material performance. Field mixing of the mulch components is acceptable, but must be done per manufacturers recommendations to ensure the proper results.

ii. All components of the hydraulically applied mulches shall be pre-packaged by the manufacturer to

- iii. Hydraulic mulches shall be applied with a viable seed and at manufacturer's recommended rates. Increased rates may be necessary based on site conditions.
- iv. Hydraulically applied mulches and additives shall be mixed according to manufacturers
- iv. Materials within this category shall only be used when hydraulically applied mulch has been specified for use on the approved Sediment and Stormwater Plan, or supplemental approval from the plan approval agency has been obtained in writing for a specific area.

So	ource:	Symbol:	Detail No.
A DOCUMENT	100 S	wind 1 streethers and the	DE-ESC-3.4.5
Delaware ESC Handbook & Filtrexx™ International		Sheet 1 of 3	
		Effective FEB 2019	

Standard Detail & Specifications Vegetative Stabilization

Seeding Mixtures		seeding Mixtures Seeding Rate ¹		Optimum Seeding Dates ² O = Optimum Planting Period A = Acceptable Planting Period							Remarks
Mix No.	Certified Seed ³			Co	astal P	lain	Piedmont		All⁴		
	Well Drained Soils	lb/Ac	lb/1000 sq.ft.	2/1- 4/30	5/1- 8/14	8/15- 10/31	3/1- 4/30	5/1- 7/31	8/1- 10/31	10/31-2/1	
1	Tall Fescue Weeping Lovegrass	140 10	3.2 0.23	Α	0	Α	Α	0	Α	Add 100 lbs./ac Winter Rye	Good erosion control mix Tolerant of low fertility soils Lovegrass very difficult to mow Germinates only in hot weather
2	Deertongue Sheep Fescue Common Lespede <i>z</i> a ⁵ Inoculated	30 30 15	0.69 0.69 0.35	Α	0	Α	Α	0	Α	Add 100 lbs./ac Winter Rye	Good erosion control mix Tolerant of low fertility soils Good wildlife cover and food
3	Tall Fescue (Turf-type) or Strong Creeping Red Fescue or Perennial Ryegrass plus Flatpea ⁵	50 50 50 15	1.15 1.15 1.15 0.34	0	Α	0	0	A	0	Add 100 lbs./ac. Winter Rye	Good erosion control mix Tall Fescue for droughty conditions. Creeping Red Fescue for heavy shade. Flatper to suppress woody vegetation.
4	Strong Creeping Red Fescue Kentucky Bluegrass Perennial Ryegrass or Redtop plus White Clover ⁵	100 70 15 5	2.3 1.61 0.35 0.11	0	Α	0	0	Α	0	Add 100 lbs./ac. Winter Rye	Suitable waterway mix. Canada Bluegrass more drought tolerant. Use Redtop for increased drought tolerance.
5	Switchgrass ^{6 7} or Coastal Panicgrass Big Bluestem Little Bluestem Indian Grass	10 10 5 5	0.23 0.23 0.11 0.11 0.1		0			0			Native warm-season mixture. Tolerant of low fertility soils. Drought tolerant. Poor shade tolerance. N fertilizer discouraged - weed
6	Tall Fescue (turf-type) (Blend of 3 cultivars)	150	3.5	0	Α	0	0	Α	0		Managed filter strip for nutrient uptake.
7	Tall Fescue Ky. Bluegrass (Blend) Perennial Ryegrass	150 20 20	3.5 0.46 0.46	0	Α	0	0	A	0		Three cultivars of Kentucky Bluegrass. Traffic tolerant.
8	Big Bluestem ⁷ Indian Grass ⁷ Little Bluestem ⁷ Creeping Red Fescue plus one of: Partridge Pea Bush Clover Wild Indigo Showy Tick-Trefoil	10 10 8 30 5 3	0.23 0.23 0.18 0.69 0.11 0.07 0.07	0	A		0	Α			All species are native. Indian Grass and Bluestem hav fluffy seeds. Plant with a specialized native seed drill. Creeping Red Fescue will provide erosion protection while the warm season grasses get established.

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.

Source:	Symbol:	Detail No.
Delaware ESC Handbook		DE-ESC-3.4.3
		Sheet 2 of 4
		Effective FEB 2019

Standard Detail & Specifications Vegetative Stabilization



	Seeding Mixtures	Seedir	ng Rate ¹		(Optimu O = Opt A = Acce	imum Pla	anting Pe	riod		Remarks
lix No.	Certified Seed ³	1		Co	astal P	lain	Р	iedmo	nt	All ⁴	
	Poorly Drained Soils	lb/Ac	lb/1000 sq.ft.	2/1- 4/30	5/1- 8/14	8/15- 10/31	3/1- 4/30	5/1- 7/31	8/1- 10/31	10/31-2/1	
9	Redtop Creeping Bentgrass Sheep Fescue Rough Bluegrass	75 35 30 45	1.72 0.8 0.69 1	0	Α	0	0	Α	0	Add 100 lbs./ac. Winter Rye	Quick stabilization of disturbed sites and waterways
10	Reed Canarygrass ^b	10	0.23	Α		0	Α		0		Good erosion control, wildlife cover and wetland revegetation
	Residential Lawns										
11	Tall Fescue Perennial Ryegrass Kentucky Bluegrass Blend	100 25 30	2.3 0.57 0.69	0	Α	0	0	Α	0		High value, high maintenance, light traffic, irrigation necessary Well drained soils, full sun.
12	Tall Fescue Perennial Ryegrass Sheep Fescue	100 25 25	2.3 0.57 0.57	0	Α	0	0	Α	0		Moderate value, low maintenance, traffic tolerant
13	Creeping Red Fescue Chewings Fescue Rough Bluegrass Kentucky Bluegrass	50 50 20 20	1.15 1.15 0.4 0.4	0	Α	0	0	Α	0		Shade tolerant, moderate traffic tolerance, moderate maintenance.
14	Creeping Red Fescue Rough Bluegrass or Chewings Fescue	50 90	1.15 2.1	0	Α	0	0	Α	0		Shade tolerant, moisture tolerant.
15	K-31 Tall Fescue	150	3.5	0	Α	0	0	Α	0		Monoculture, but performs well alone in lawns. Discouraged.

1. When hydroseeding is the chosen method of application, the total rate of seed should be increased by 25%.
2. Winter seeding requires 3 tons per acre of straw mulch. Planting dates listed above are average for Delaware. These dates may require adjustment to 3. All seed shall meet the minimum purity and minimum germination percentages recommended by the Delaware Department of Agriculture. The maximum % of weed seeds shall be in accordance with Section 1, Chapter 24, Title 3 of the Delaware Code.

4. Cool season species may be planted throughout summer if soil moisture is adequate or seeded area can be irrigated

i. Warm season grass mix and Reed Canary Grass cannot be mowed more than 4 times per year. 7. Warm season grasses require a soil temperature of at least 50 degrees in order to germinate, and will remain dormant until then

NOTE: Alternative seed mixes may be used with prior approval from the Department or Delegated Agency

Source:	Symbol:	Detail No.
Delaware ESC Handbook		DE-ESC-3.4.3
		Sheet 3 of 4
		Effective FEB 2019



	Seeding Mixtures	Seeding Rate ¹			Seeding Rate ¹ Optimum Seeding Dates ² O = Optimum Planting Period A = Acceptable Planting Period						Remarks
Mix No.	Certified Seed ³	Ï		Co	astal P	lain	Р	iedmo	nt	Ali⁴	
	Poorly Drained Soils	lb/Ac	lb/1000 sq.ft.	2/1- 4/30	5/1- 8/14	8/15- 10/31	3/1- 4/30	5/1- 7/31	8/1- 10/31	10/31-2/1	
9	Redtop Creeping Bentgrass Sheep Fescue Rough Bluegrass	75 35 30 45	1.72 0.8 0.69 1	0	Α	0	0	Α	0	Add 100 lbs./ac. Winter Rye	Quick stabilization of disturbed sites and waterways
10	Reed Canarygrass ^b	10	0.23	Α		0	Α		0		Good erosion control, wildlife cover and wetland revegetation
	Residential Lawns										50.
11	Tall Fescue Perennial Ryegrass Kentucky Bluegrass Blend	100 25 30	2.3 0.57 0.69	0	Α	0	0	Α	0		High value, high maintenance, light traffic, irrigation necessary. Well drained soils, full sun.
12	Tall Fescue Perennial Ryegrass Sheep Fescue	100 25 25	2.3 0.57 0.57	0	Α	0	0	Α	0		Moderate value, low maintenance, traffic tolerant
13	Creeping Red Fescue Chewings Fescue Rough Bluegrass Kentucky Bluegrass	50 50 20 20	1.15 1.15 0.4 0.4	0	Α	0	0	Α	0		Shade tolerant, moderate traffic tolerance, moderate maintenance.
14	Creeping Red Fescue Rough Bluegrass or Chewings Fescue	50 90	1.15 2.1	0	Α	0	0	Α	0		Shade tolerant, moisture tolerant.
15	K-31 Tall Fescue	150	3.5	0	Α	0	0	Α	0		Monoculture, but performs well

All leguminous seed must be inoculated.

Standard Detail & Specifications Vegetative Stabilization

Construction Notes:

. Site Preparation

- a. Prior to seeding, install needed erosion and sediment control practices such as diversions, grade stabilization structures, berms, dikes, grassed waterways, and sediment basins.
- b. Final grading and shaping is not necessary for temporary seedings.

Seedbed Preparation

It is important to prepare a good seedbed to insure the success of establishing vegetation. The seedbed should be well prepared, loose, uniform, and free of large clods, rocks, and other objectionable material. The soil surface should not be compacted or crusted.

3. Soil Amendments

- a. Lime Apply liming materials based on the recommendations of a soil test in accordance with the approved nutrient management plan. If a nutrient management plan is not required, apply dolomitic limestone at the rate of 1 to 2 tons per acre. Apply limestone uniformly and incorporate into the top 4 to 6 inches of soil.
- b. Fertilizer Apply fertilizer based on the recommendations of a soil test in accordance with the approved nutrient management plan. If a nutrient management plan is not required, apply a formulation of 10-10-10 at the rate of 600 pounds per acre. Apply fertilizer uniformly and incorporate into the top 4 to 6 inches of soils.

- a. For temporary stabilization, select a mixture from Sheet 1. For a permanent stabilization, select a mixture from **Sheet 2** or **Sheet 3** depending on the conditions. Alternative seed mixes may be used with prior approval from the Department or Delegated Agency.
- b. Apply seed uniformly with a broadcast seeder, drill, cultipacker seeder or hydroseeder. All seed will be applied at the recommended rate and planting depth.
- Seed that has been broadcast should be covered by raking or dragging and then <u>lightly</u> tamped into place using a roller or cultipacker. If hydroseeding is used and the seed and fertilizer is mixed, they will be mixed on site and the seeding shall be done immediately and without interruption.

5. Mulching

All mulching shall be done in accordance with detail **DE-ESC-3.4.5**.


Source:	Symbol:	Detail No.
Delaware ESC Handbook		DE-ESC-3.4.3
		Sheet 4 of 4
		Effective FEB 2019

Standard Detail & Specifications Mulching

- - a. Apply product to geotechnically stable slopes that have been designed and constructed to divert runoff away from the face of the slope.
 - b. Do not apply to saturated soils, or if precipitation is anticipated within 24-48 hours.
 - c. During the spring (March 1 to May 31) and fall (September 1 to November 30) seasons, hydraulic mulches may be applied in a one-step process where all components are mixed together in single-tank loads. It is recommended that the product be applied from opposing directions to achieve optimum soil coverage.
 - d. During the summer (June 1 to August 31) and winter (December 1 to February 28) seasons, the following two-step process is required:
 - Step One-Mix and apply seed and soil amendments with a small amount of mulch for
 - <u>Step Two</u> Mix and apply mulch at manufacturers recommended rates over freshly seeded surfaces. Apply from opposing directions to achieve optimum soil coverage.
 - e. Minimum curing temperature is 40°F (4°C). The best results and more rapid curing are achieved at temperatures exceeding 60°F (15°C). Curing times may be accelerated in high temperature, low humidity conditions on dry soils.
- vi. Recommended application rates are for informational purposes only. Conformance with this standard and specification shall be performance-based and requires **100% soil coverage**. Any areas with bare soil showing shall be top dressed until full coverage is achieved.
- d. Compost blanket (CB) Loosely applied with a pneumatic blower so that a 1" compost blanket uniformly covers the **soil with 100% coverage**. This application can be used with seed to promote germination by applying the approved seed mix directly into the loosely blown compost. The compost blanket performs best on slopes less than 2:1 and requires no mulch anchoring.
- **Anchoring mulch** Mulch must be anchored immediately to minimize loss by wind or water. This may be done by one of the following methods, depending upon size of area, erosion hazard, and cost.
- a. Crimping A crimper is a tractor drawn implement designed to punch and anchor mulch into the top two (2) inches of soil. This practice affords maximum erosion control but is limited to flatter slopes where equipment can operate safely. On sloping land, crimping should be done on the contour whenever possible.
- b. Tracking Tracking is the process of cutting mulch (usually straw) into the soil using a bulldozer or other equipment that runs on cleated tracks. Tracking is used primarily on slopes 3:1 or steeper and should be done up and down the slope with cleat marks running across the slope.
- c. Liquid mulch binders Applications of liquid mulch binders should be heavier at edges, in valleys, and at crests of banks and other areas where the mulch will be moved by wind or water. All other areas should have a uniform application of binder. The use of synthetic binders is the preferred method of mulch binding and should be applied at the rates recommended by the manufacturer.
- d. Paper fiber The fiber binder shall be applied at a net dry weight of 750 lbs/ac. The wood cellulose fiber shall be mixed with water, and the mixture shall contain a maximum of 50 lbs. of wood cellulose fiber per
- e. Nettings Synthetic or organic nettings may be used to secure straw mulch. Install and secure according to the manufacturers recommendations.

ource:	Symbol:	Detail No.
Delaware ESC Handbook & Filtrexx™ International		DE-ESC-3.4.5 Sheet 2 of 3
		Effective FEB 2019

Standard Detail & Specifications Mulching



Source:	Symbol:	Detail No.
Delaware ESC Handbook & Filtrexx™ International		DE-ESC-3.4.5
		Sheet 3 of 3
		Effective FEB 2019

SEEDING AND MULCHING NOTES:

DITCH AREAS: NON-DITCH DISTURBED AREAS: DE. SEED MIX #9 OR 14 DE SEED MIX #11

ERNST SEED MIX - RETENTION BASIN FLOOR MIX - ERNMX-126

SEED MUST BE APPLIED PER MANUFACTURER'S RECOMMENDED RATE.

IN ALL NON-AGRICULTURAL AREAS, MULCHING MEETING THE REQUIREMENTS OF DE-ESC-3.4.5 OR STABILIZATION MATTING MEETING THE REQUIREMENTS OF DE-ESC-3.4.6 MUST BE USED.

STRAW MULCH SHALL BE USED IN DISTURBED AREA ON RESIDENTIAL LOTS. DITCHES SHALL BE MATTED PER THE TYPICAL DITCH CROSS SECTION NOTES

TOPSOILING NOTES:

COORDINATE WITH DNREC AND LANDOWNER FOR DIRECTION ON STOCKPILED TOPSOIL DISPOSAL MEANS:



DNREC

NNCHESTER IN AGE IMPROVEME CREEK / NANTICOKUSEX COUNTY, DE

2/04/2022

nned: JE / KW / JG / TB

C-705

CONSTRUCTION NOTES:

- 1. EXISTING UTILITIES ARE SHOWN IN ACCORDANCE WITH THE BEST AVAILABLE INFORMATION. COMPLETENESS OR CORRECTNESS THEREOF IS NOT GUARANTEED. IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO CONTACT THE UTILITY COMPANIES INVOLVED IN ORDER TO SECURE THE MOST ACCURATE INFORMATION AVAILABLE AS TO UTILITY LOCATION AND ELEVATION. NO CONSTRUCTION AROUND OR ADJACENT TO UTILITIES SHALL BEGIN WITHOUT NOTIFYING THEIR OWNERS AT LEAST 48 HOURS IN ADVANCE. THE CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND MAINTAIN UNINTERRUPTED SERVICE AND ANY DAMAGE DONE TO THEM DUE TO HIS NEGLIGENCE SHALL BE IMMEDIATELY AND COMPLETELY REPAIRED AT THE CONTRACTOR'S EXPENSE. TO LOCATE EXISTING UTILITIES IN THE FIELD PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONTACT MISS UTILITY OF DELMARVA AT 1-800-282-8555.
- 2. THE SITE SHALL BE GRADED TO THE FINAL ELEVATIONS SHOWN ON THE STORMWATER MANAGEMENT, GRADING, EROSION AND SEDIMENT CONTROL PLAN PREPARED BY SCD. THE CONTRACTOR SHALL PERFORM GRADING TO PROVIDE POSITIVE DRAINAGE AND PRECLUDE PONDING OF WATER.
- 3. THE CONTRACTOR WILL BE RESPONSIBLE FOR CLEARING AND GRADING AND GRUBBING THE SITE TO LIMITS SHOWN ON THE PLANS. THIS WILL INCLUDE THE REMOVAL AND DISPOSAL OF ANY EXISTING PAVEMENT, FENCES, BUILDING DEBRIS AND TRASH ON THE SITE. DISPOSAL WILL BE OFF—SITE IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS; AND AT THE CONTRACTOR'S EXPENSE.
- 4. THE CONTRACTOR SHALL EXERCISE CARE AND CONSIDERATION IN CONSTRUCTION IN THE VICINITY OF ADJACENT PROPERTY OWNERS.
- 5. ALL DISTURBED R.O.W./PROPERTY CORNER MONUMENTS ARE TO BE VERIFIED BY A PROFESSIONAL ENGINEER OR A REGISTERED PROFESSIONAL LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE AND REPLACED/RESET IF NEEDED.
- 6. RIPRAP ROCK SHALL AS A MINIMUM: D50 STONE SIZE = 6", DEPTH = 18".
- 7. ALL REMAINING SPOILS AFTER BULK GRADING IS COMPLETED SHALL BE REMOVED OFF SITE IN AN APPROVED MANNER.
- 8. DUST CONTROL DURING DEMOLITION AND CONSTRUCTION CONTRACTOR IS RESPONSIBLE FOR WETTING DUST GENERATING DEBRIS FROM TIME OF FIRST CONTACT UNTIL PLACING INTO APPROPRIATE WASTE OR HAULING CONTAINERS OR TRUCKS. DEBRIS SHALL NOT BE ALLOWED TO DRY BEFORE REMOVED FROM SITE. REFER TO DETAIL DE—ESC 3.4.8 SHEET CS8502 FOR ADDITIONAL INFORMATION. THIS PRACTICE SHALL ALSO BE FOLLOWED FOR ANY BARE SOIL LEFT EXPOSED PRIOR TO PROPER VEGETATION OCCURS.
- 9. ALL MATERIALS AND WORKMANSHIP WITHIN THE STATE OF DELAWARE RIGHT—OF—WAY SHALL BE IN ACCORDANCE WITH CURRENT STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, SUPPLEMENTAL SPECIFICATIONS, STANDARD CONSTRUCTION DETAILS, SPECIAL PROVISIONS, PAS MANUAL AND DESIGN GUIDANCE MEMORANDUMS.
- 10. ALL NYLOPLAST BASINS AND INLINE DRAIN BASINS INSTALLED W/IN THE DeIDOT RIGHT—A—WAY SHALL BE INSTALL PER THE NYLOPLAST H—20 TRAFFIC LOADING INSTALLATION DETAIL W/ CONC. COLLAR.
- 11. ALL DRIVEWAYS SHALL BE REPLACED AND OR REPAIRED IN KIND. COORDINATE WITH OWNER TO MAINTAIN ACCESS TO RESPECTIVE PROPERTIES.
- 12. ALL MAILBOXES SHALL BE REPLACED AND OR REPAIRED IN KIND. COORDINATE WITH OWNER TO MAINTAIN MAIL SERVICE DURING CONSTRUCTION.
- 13. PROJECT STAKED OUT IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 14. ELEVATIONS ARE BASED ON NAVD 88, AND DE STATE PLANE COORDINATE SYSTEM NAD 83 HORIZONTAL DATUM.
- 15. UNLESS SPECIFICALLY STATED OR SHOWN HEREON TO THE CONTRARY, THIS SURVEY IS MADE SUBJECT TO AND DOES NOT LOCATE OR DELINEATE:
- 15.1. RIGHTS OR INTEREST OF THE UNITED STATES OF AMERICA OR STATE OF DELAWARE OVER LANDS NOW OR FORMERLY FLOWED BY TIDEWATER, BUT NO LONGER VISIBLE OR PHYSICALLY EVIDENT, OR LANDS CONTAINING ANY ANIMAL, MARINE OR BOTANICAL SPECIES REGULATED BY OR UNDER THE JURISDICTION OR ANY FEDERAL, STATE, OR LOCAL AGENCY.

15.2. BUILDING SETBACK LINES, ZONING REGULATIONS OR LINES ESTABLISHED BY ANY FEDERAL, STATE OR LOCAL AGENCY WHICH MAY AFFECT THE BUILDING OR DEVELOPMENT POTENTIAL OF THE SUBJECT PROPERTY.

15.3. ANY SUBSURFACE OR SUBTERRANEAN CONDITION, EASEMENTS OR RIGHTS, INCLUDING, BUT NOT LIMITED TO MINERAL OR MINING RIGHTS, OR THE LOCATION OF OR RIGHTS TO ANY SUBSURFACE STRUCTURES, CONTAINERS OR FACILITIES OR ANY OTHER NATURAL OR MAN-MADE SUBSURFACE CONDITION WHICH MAY OR MAY NOT AFFECT THE USE OR DEVELOPMENT POTENTIAL OF THE SUBJECT PROPERTY.

16. UTILITY NOTES:

16.1. THE LOCATION OF THE EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN HAVE BEEN TAKEN FROM EXISTING UTILITY RECORDS AVAILABLE AT THE TIME THESE PLANS WERE PREPARED AND FROM SURFACE OBSERVATION OF THE SITE. LOCATIONS OF UTILITIES AS SHOWN AND MAY OR MAY NOT BE COMPLETE. THE NATURE AND EXACT LOCATION OF EXISTING UTILITIES SHOULD BE VERIFIED PRIOR TO INITIATING ANY ACTIVITY THAT MAY AFFECT THEIR USE OR LOCATION.

- 16.2. COMPLETENESS OR ACCURACY OF LOCATION AND DEPTH OF UNDERGROUND UTILITIES AND STRUCTURES IS NOT GUARANTEED.
- 16.3. MISS UTILITY SHALL BE NOTIFIED THREE (3) DAYS PRIOR TO EXCAVATION.
- 16.4. THE CONTRACTORS SHALL TEST PIT TO VERIFY LOCATIONS AND DEPTHS OF ALL UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF
- 16.5. IF CONFLICTS ARE FOUND THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER AND DESIGN ENGINEER FOR INSTRUCTION BEFORE PROCEEDING WITH WORK.
- 17. STATE WETLAND FLAG SHOWN WAS PER DNREC DRAINAGE SECTION DELINEATION.
- REFERENCE:
- 18. EXISTING CONDITIONS SURVEY PERFORMED BY RAUCH ENG..
- 19. THE PARCEL BOUNDARY LINES ARE FROM BEST AVAILABLE GIS DATA.

EROSION AND SEDIMENT CONTROL GENERAL NOTES:

- 1. THE DNREC SEDIMENT AND STORMWATER MANAGEMENT PROGRAM MUST BE NOTIFIED IN WRITING FIVE (5) DAYS PRIOR TO COMMENCING WITH CONSTRUCTION.
- FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.
- 2. REVIEW AND OR APPROVAL OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM HIS OR HER RESPONSIBILITIES FOR COMPLIANCE WITH THE REQUIREMENTS OF THE SEDIMENT AND STORMWATER REGULATIONS, NOR SHALL IT RELIEVE THE CONTRACTOR FROM ERRORS OR OMISSIONS IN THE APPROVED PLAN.
- 3. IF THE APPROVED PLAN NEEDS TO BE MODIFIED, ADDITIONAL SEDIMENT AND STORMWATER CONTROL MEASURES MAY BE REQUIRED AS DEEMED NECESSARY BY DNREC.
- 4. FOLLOWING SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED FOR ALL PERIMETER SEDIMENT CONTROLS, SOIL STOCKPILES, AND ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE WITHIN 14 CALENDAR DAYS UNLESS MORE RESTRICTIVE FEDERAL REQUIREMENTS APPLY, OR IF A MORE RESTRICTIVE REQUIREMENT'S NOTED ON THE PLANS.
- 5. ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL COMPLY WITH THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.
 6. AT ANY TIME A DEWATERING OPERATION IS USED, IT SHALL BE PREVIOUSLY APPROVED BY THE AGENCY CONSTRUCTION SITE REVIEWER FOR A NON-EROSIVE POINT OF DISCHARGE, AND A DEWATERING PERMIT SHALL BE APPROVED BY THE DNREC WELL PERMITTING BRANCH.
 7. APPROVED PLANS REMAIN VALID FOR 3 YEARS FROM THE DATE OF APPROVAL.
- 8. THE NOTICE OF INTENT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER A NPDES GENERAL PERMIT FOR THIS PROJECT IS #_?????? . AT ANY TIME THE OWNERSHIP FOR THIS PROJECT CHANGES, A TRANSFER OF AUTHORIZATION OR A CO-PERMITTEE APPLICATION MUST BE SUBMITTED TO DNREC. THE PERMITTEE OF RECORD SHALL NOT BE RELIEVED OF THEIR RESPONSIBILITIES UNTIL A NOTICE OF TERMINATION HAS BEEN PROCESSED BY DNREC.
- 9. THE OWNER SHALL BE FAMILIAR WITH AND COMPLY WITH ALL ASPECTS OF THE NPDES CONSTRUCTION GENERAL PERMIT ASSOCIATED WITH THE PROJECT, INCLUDING, BUT NOT LIMITED TO, PERFORMING WEEKLY SITE INSPECTIONS DURING CONSTRUCTION AND AFTER RAIN EVENTS, AND MAINTAINING WRITTEN LOGS OF THESE INSPECTIONS.
- 10. BEFORE ANY EARTHWORK OR EXCAVATION TAKES PLACE, THE CONTRACTOR SHALL CALL MISS UTILITY AT 811 OR 1.800.282.8555 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION, TO HAVE ALL EXISTING UTILITIES MARKED ONSITE.
- 11. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT OF DEBRIS LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHALL BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENT FROM LEAVING THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST OR ALTER MEASURES IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE AGENCY SITE REVIEWER.
- 12. BEST AVAILABLE TECHNOLOGY (BAT) SHALL BE EMPLOYED TO MANAGE TURBID DISCHARGES IN ACCORDANCE WITH REQUIREMENTS OF 7. DEL C. CH 60, REGULATIONS GOVERNING THE CONTROL OF WATER POLLUTION, SECTION 9.1.02, KNOWN AS SPECIAL CONDITIONS FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES AND DEPARTMENT POLICIES, PROCEDURES, AND GUIDANCE.
- 13. DOCUMENTATION OF SOIL TESTING AND MATERIALS USED FOR TEMPORARY OR PERMANENT STABILIZATION INCLUDING BUT NOT LIMITED TO SOIL TEST RESULTS, SEED TAGS, SOIL AMENDMENT TAGS, ETC, SHALL BE PROVIDED TO THE DEPARTMENT OR DELEGATED AGENCY TO VERIFY THAT THE PERMANENT OR TEMPORARY STABILIZATION HAS BEEN COMPLETED IN ACCORDANCE WITH THE APPROVED PLAN AND THE STANDARDS AND SPECIFICATIONS OF THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION. THE DEPARTMENT OF THE DELEGATED AGENCY SHALL HAVE THE DISCRETION TO REQUIRE ADDITIONAL SOIL TESTING AND REAPPLICATION OF PERMANENT OR TEMPORARY STABILIZATION IN ACCORDANCE WITH THE SPECIFICATION PROVIDED WITHIN THE DELAWARE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.

GRADING NOTES:

1. BEDDING REQUIREMENTS SPECIFIED HEREIN ARE TO BE CONSIDERED AS MINIMUMS FOR RELATIVELY DRY, STABLE EARTH CONDITIONS. ADDITIONAL BEDDING SHALL BE REQUIRED FOR ROCK TRENCHES AND WET AREAS. CONTRACTOR SHALL HAVE THE RESPONSIBILITY TO PROVIDE SUCH ADDITIONAL BEDDING AS MAY BE REQUIRED TO PROPERLY CONSTRUCT THE WORK.

- 2. COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF THEORETICAL MAXIMUM DRY DENSITY (ASTM D698).
 BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS AND SHALL BE PLACED IN LIFTS NOT TO EXCEED 8 INCHES IN COMPACTED FILL THICKNESS. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. MATERIAL THAT CANNOT BE COMPACTED AS REQUIRED SHALL BE BROUGHT TO THE ATTENTION OF A GEO-TECHNICAL ENGINEER, OVER EXCAVATED, AND THEN REPLACED WITH SUITABLE FILL
- 3. THE CONTRACTOR WILL INSURE THAT POSITIVE AND ADEQUATE DRAINAGE IS MAINTAINED AT ALL TIMES WITHIN THE PROJECT LIMITS. THIS MAY INCLUDE, BUT NOT BE LIMITED TO, REPLACEMENT OR RECONSTRUCTION OF EXISTING DRAINAGE STRUCTURES THAT HAVE BEEN DAMAGED OR REMOVED OR REGRADING AS REQUIRED BY THE ENGINEER, EXCEPT FOR THOSE DRAINAGE ITEMS SHOWN AT SPECIFIC LOCATIONS AND HAVING SPECIFIC PAY ITEMS IN THE DETAILED ESTIMATE. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COSTS INCURRED TO COMPLY WITH THIS REQUIREMENT.
- 4. THE CONTRACTOR SHALL PROVIDE ANY AND ALL EXCAVATION AND MATERIAL SAMPLES NECESSARY TO CONDUCT REQUIRED SOIL TESTS. ALL ARRANGEMENTS AND SCHEDULING FOR THE TESTING SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- 5. SOILS TESTING AND ON-SITE INSPECTION SHALL BE PERFORMED BY AN INDEPENDENT GEOTECHNICAL ENGINEER. THE SOILS ENGINEER SHALL PROVIDE COPIES OF TEST REPORTS TO THE CONTRACTOR, THE OWNER AND THE OWNER'S REPRESENTATIVE AND SHALL PROMPTLY NOTIFY THE OWNER, HIS REPRESENTATIVE AND THE CONTRACTOR, SHOULD WORK PERFORMED BY THE CONTRACTOR FAIL TO MEET BUILDING STANDARDS.
- 6. CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES AROUND THE WORK AREA AND SHALL PROVIDE PROTECTION AGAINST WATER DAMAGE AND SOIL EROSION.
- 7. VERTICAL ELEVATIONS ARE BASED ON NAVD 88.
- 8. ALL SLOPES MAXIMUM 3:1 UNLESS OTHERWISE NOTED.

9. HDPE PIPE SHALL COMPLY WITH AASHTO M252, M294, MP7, AND ASTM 3350. PIPE SHALL BE INSTALLED PER ASTM D2321 AND AS RECOMMENDED BY THE MANUFACTURER. ALL HDPE SHALL HAVE SOIL TIGHT CONNECTIONS.

- 10. ALL MATERIALS AND WORKMANSHIP WITHIN THE STATE OF DELAWARE RIGHT—OF—WAY SHALL BE IN ACCORDANCE WITH CURRENT STATE OF DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, SUPPLEMENTAL SPECIFICATIONS, STANDARD CONSTRUCTION DETAILS, SPECIAL PROVISIONS, PAS MANUAL AND DESIGN GUIDANCE MEMORANDUMS.
- 11. DRAINAGE INLETS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE LATEST STANDARDS OF DELDOT'S STANDARD CONSTRUCTION DETAILS UNLESS NOTED OTHERWISE ON THE PLANS.
- 12. ALL HDPE PIPE SHALL MEET OR EXCEED THAT AASHTO M-330 PIPE SPECIFICATION.

13. CONTRACTOR IS RESPONSIBLE FOR REMOVING AND DISPOSING OF EXCESS DIRT FROM THE SITE. THIS CAN BE COORDINATED WITH OWNER TO DETERMINE IF LONG TERM STORAGE ON SITE IS APPLICABLE.

14. CONTRACTOR IS RESPONSIBLE TO ENSURE POSITIVE DRAINAGE AND PREVENT PONDING FOR ALL PROPOSED IMPROVEMENTS ALONG WITH NOT NEGATIVE IMPACTING EXISTING CONDITIONS. CONTRACTOR MUST DISCUSS WITH THE DESIGN ENGINEER IF FIELD ISSUES ARISE, IF AT TIME OF STAKEOUT. IF NOT THE OWNS IT.

CONTROL SEQUENCE OF CONSTRUCTION:

- 1. NOTIFY THE DNREC DRAINAGE PROGRAM IN WRITING AT LEAST FIVE (5) DAYS PRIOR TO THE START OF CONSTRUCTION. FAILURE TO DO SO CONSTITUTES A VIOLATION OF THE APPROVED SEDIMENT AND STORMWATER MANAGEMENT PLAN.
- 2. PRIOR TO ANY CLEARING, INSTALLATION OF SEDIMENT CONTROL MEASURES, OR GRADING, A PRE-CONSTRUCTION MEETING MUST BE CONDUCTED WITH THE CONSTRUCTION SITE REVIEWER. THE LANDOWNER, CONTRACTOR AND CERTIFIED CONSTRUCTION REVIEWER ARE REQUIRED TO BE IN ATTENDANCE AT THE PRE-CONSTRUCTION MEETING; THE DESIGNER IS RECOMMENDED TO ATTEND.
- 3. INSTALL THE STABILIZED CONSTRUCTION ENTRANCE(S) AS INDICATED ON THE PLAN, FOLLOWED BY THE PERIMETER CONTROLS (I.E., BERMS, SILT FENCE, COMPOST LOGS) AND INLET PROTECTION ON ANY EXISTING INLETS. MARK THE LIMITS OF SENSITIVE AREAS, SUCH AS PRESERVED TREES, INFILTRATION AREAS, AND OTHER SECTIONS THAT ARE NOT TO BE DISTURBED WITH A PHYSICAL BARRIER. ONLY CLEAR WOODS THAT ARE NEEDED TO INSTALL THE PERIMETER CONTROLS.
- 4. SCHEDULE A PERIMETER CONTROL REVIEW WITH THE DNREC CONSTRUCTION SITE REVIEWER.
- 5. ALL PERIMETER CONTROLS ARE TO BE REVIEWED BY THE DNREC CONSTRUCTION SITE REVIEWER AND APPROVED PRIOR TO PROCEEDING WITH FURTHER SITE DISTURBANCE OR CONSTRUCTION
- 6. THE CONTRACTOR SHALL AT ALL TIMES PROTECT AGAINST SEDIMENT LADEN RUNOFF OR WIND FROM LEAVING THE SITE. PERIMETER CONTROLS SHOULD BE CHECKED DAILY AND ADJUSTED AND/OR REPAIRED TO FULLY CONTAIN AND CONTROL SEDIMENTATION ON THE SITE. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED HALF OF THE EFFECTIVE CAPACITY OF THE CONTROL. IN ADDITION, THE CONTRACTOR MAY NEED TO ADJUST, REPAIR OR ALTER MEASURES IN TIMES OF ADVERSE WEATHER CONDITIONS, OR AS DIRECTED BY THE DNREC CONSTRUCTION SITE REVIEWER.
- 7. CLEAR AND GRUB THE CONSTRUCTION AREA.
- 8. STOCKPILE TOPSOIL AND EXCAVATED SUBSOILS. STOCKPILES SHOULD BE SURROUNDED WITH A PERIMETER CONTROL, LOCATED ON LAND WITH SLIGHT TO NO SLOPE, AND STABILIZED ONCE INACTIVE. COORDINATE WITH LANDOWNER FOR LAY DOWN AND STOCKPILE AREA.
- 9. REMOVE AND REPLACE SWM POND OUTFALL PIPE AND STRUCTURE.
- 10. RECONSTRUCT SWM POND FOREBAY, STILLING BASIN, AND CONNECTING LOW FLOW CHANNEL PER THE PLAN. RIPRAP OUTFALL AND INFLOW PIPES ENDS.
- 11. CONSTRUCT THE STORM DRAIN PIPE SYSTEM WORKING IN A DOWNSTREAM TO UPSTREAM DIRECTION. INSTALL INLET PROTECTION ON ALL INLETS AFTER THEY
- 12. CONSTRUCT STORMWATER CONVEYANCE SYSTEM THAT DISCHARGES TO THE PUMP STATION, STARTING AT THE LOWEST ELEVATION WITHIN THE NETWORK AND WORKING UPWARDS. INSTALL NECESSARY EROSION AND SEDIMENT CONTROL PROTECTION AS SHOWN ON PLAN.
- 12.1) INSTALL ALL STORM DRAIN PIPE. PLACE IP1 AROUND NYLOPLAST BASINS AND PLACE CFL IN FRONT OF ALL INFLOW POINTS / FES(s).
- 12.2) CONSTRUCT DITCHES AND SWALES THAT TIE INTO STORM DRAIN NETWORK TO THE DIMENSIONS SHOWN ON THE PLAN
- 12.3) STABILIZE AND PROVIDE MATTING FOR ALL DITCHES PER THE TYPICAL CROSS SECTION SPECS.
- 12.4) STABILIZE ALL SWALES PER THE TYPICAL CROSS SECTION SPECS.
- 12.5) REGRADE ROAD SIDE SWALES TO THE ELEVATIONS SHOWN ON THE PLAN. REMOVE AND REPLACE DRIVEWAY CULVERTS PER THE APPROPRIATE PROFILES.
- 12.6) STABILZE ALL SWALES PER THE TYPICAL CROSS SECTION SPECS.
- 12.7) CONSTRUCT LANDSCAPE BUFFER DITCH, DITCH 3, AND DITCH 4.
- 12.8) FINAL GRADE ALL DITCHES AND DISTURBED AREAS AND APPLY PERMANENT SEEDING AND STABILIZATION AS SOON AS FINAL GRADE IS ACHIEVED.
- 13. THE EROSION AND SEDIMENT CONTROL DEVICES SHOULD BE REMOVED ONLY AFTER WORK IN AN AREA HAS BEEN COMPLETED AND STABILIZED, WITH WRITTEN APPROVAL FROM THE DNREC CONSTRUCTION SITE REVIEWER. COORDINATE THE INSPECTION, AND AFTER THE WRITTEN APPROVAL, REMOVE THE REMAINING CONSTRUCTION SITE CONTROLS.
- 14. TERMINATE COVERAGE OF THE CONSTRUCTION GENERAL PERMIT, WHICH REQUIRES SUBMISSION AND ACCEPTANCE OF THE POST CONSTRUCTION VERIFICATION DOCUMENTS, INCLUDING FINAL STABILIZATION THROUGHOUT THE SITE, ALL ELEMENTS OF THE SEDIMENT AND STORMWATER MANAGEMENT PLAN IMPLEMENTED, ACCEPTANCE OF THE FINAL OPERATION AND MAINTENANCE PLAN, AND SUBMITTAL OF THE NOTICE OF TERMINATION.

REVISIONS

DESCRIPTION
design gravity option
C COMMENTS
EC COMMENTS
EC COMMENTS
EC COMMENTS

10.22 re-design 10.22 DNREC CON 11.8.22 DNREC CO 12.9.22 DNREC CO



n of Watershed Stewardship inage Program
Georgetown Office
739-9921 21309 Berlin Rd. Unit 6 Phone: (302) 855-

SUSSI 2381 DNREC -

SELECTION WITHOUT OF W


HESTER MANOR
IMPROVEMENTS, # 21-229
IMPROVEMENTS, # 21-229
IMPROVEMENTS, # 21-229
COUNTY, DELAWARE


DRAINAGE IMPRC
BROAD CREEK / NAN
SUSSEX COUN

2/04/2022

Planned: JE/KW/JG/TB

Sheet No. **C-706**





Symbol:

Source:

Adapted from

Colorado Urban Storm Drainage


Criteria Manual, Vol 3

Detail No.


DE-ESC-3.7.3

Sheet 2 of 2


Effective FEB 2019




Effective February 2019




Effective February 2019



Effective February 2019



Effective February 2019



CONSERVATION DISTRICT. PREFERVE.

S18 SHORTLY RD., GEORGETOWN, DE 19957
PHONE: (302)-856-2105 FAX: (302-856-0951
- Division of Watershed Stewards
Drainage Program
Georgetown Office

SANTHENT OF MITTERS

DNREC

MANCHESTER MANOR
DRAINAGE IMPROVEMENTS, # 21-229
BROAD CREEK / NANTICOKE WATERSHED
SUSSEX COUNTY, DELAWARE
EROSION & SEDIMENT CONTROL
DETAILS AND NOTES

2/04/2022 ned: JE

Planned: JE / KW / JG / TB

Drawn: JE

No. **C-707**